



# **Retrieval of Fuel Debris**

**- Report from Sub-Committee for the Evaluation of Fuel Debris Retrieval Methods -**

Toyoshi Fuketa

The 9th International Forum on the Decommissioning of  
the Fukushima Daiichi Nuclear Power Station


August 3, 2025

Katsurao Village Junior High School

# Fuel Debris

- ✓ Debris means “wreckage and fragments”.
- ✓ Nuclear fuel that has melted, flowed down, collapsed, or mixed with surrounding structures as a result of the accident is called "fuel debris”.
- ✓ At present, the fuel debris is stable and not in a state that requires urgent action.
- ✓ In the long term, it is important to retrieve fuel debris and transfer it to a properly controlled condition.
- ✓ The purpose is to transfer the radioactive material in a dispersed state to a sufficiently stable state. Removal of fission products (FP) including cesium is also important.

# Fuel Debris at Fukushima Daiichi



Images courtesy of TEPCO Holdings, Inc.

- ✓ Full-scale retrieval starts with Unit 3.
- ✓ Properties and distribution of fuel debris greatly vary depending on the accident progression.


Nearly intact stump-shaped fuel rod, fallen gravel-like fuel pellets, melted and solidified metal/ceramic materials, FP stuck in narrow segments, etc.

# Internal Investigation

Drone



ROV



Robot arm







Video



Noise  
removal



Point cloud  
data



Engineering study using 3D models


Creating 3D models from video and point cloud data




# Fuel Debris Retrieval

✓ Engineering study based on partial submersion method is underway


## Partial submersion method



## Submersion method



# Top Access and Side Access in Partial Submersion Method




→ Fuel debris retrieval route

- ✓ Top access from small opening
- ✓ Continuous collections of debris that are cut into small pieces
- ✓ Combination of top access and side access


# Support Structures for Top Access

- ✓ Two plans are under consideration: North-South platform and East-West gantry.
- ✓ Environmental improvements of the surrounding area is a major issue

## North-South platform plan




## East-West gantry plan





# Environmental Improvement In and Around the Reactor Building

Dose rate on the first floor of Unit-3 R/B



Facilities surrounding Unit-3 R/B



- ✓ Does levels reach nearly 100 mSv/h in some areas on the first floor of Unit-3 R/B
- ✓ There are multiple facilities surrounding the R/B, which interfere with the work



# Main Process for Fuel Debris Retrieval

## Main process


Environmental improvement

Internal investigation/sampling

Fuel debris retrieval

Transfer

Storage



Integrated monitoring facility

Outdoor

Pre-storage treatment facility

Storage facility

Control room

## Sub process

Removal of interfering objects outside the reactor building

1st floor dose reduction, removal of interfering objects

RPV internal investigation

PCV internal investigation

Processing

Collection

Pre-transfer treatment

Delivery

Transfer

Receiving

Pre storage treatment

Storage

# Summary

- ✓ In July of this year, TEPCO reported progress on engineering study to the Sub-Committee and the following topics were discussed:
  - Combination of top access and side access
  - Support structures for top access  
(North-South platform and East-West Gantry plan)
  - Environmental improvement in and around the reactor building
- ✓ Environmental Improvement such as dismantling and removal of surrounding facilities are critical issues that should be prioritized from a safety perspective
- ✓ Regarding the fundamental approach to ensuring safety, discussions and considerations with a more long-term perspective than before are required



**Thank you for your attention.**

