

# **Revision of the Mid-term Risk Reduction Target for TEPCO's Fukushima Daiichi Nuclear Power Station**

**August 6, 2018**

**Hiroshi YAMAGATA**

**Director-General for Emergency Response**

**The Secretariat of Nuclear Regulation Authority**

# Contents




- What is Mid-term Risk Reduction Target?
- Concepts of the Revision of March 2018 Version
- Revision of the Mid-term Risk Reduction Target
- Priority Items
- Summary

# Mid-term Risk Reduction Target



➤ Nuclear Regulation Authority(NRA) formulated the “Mid-term Risk Reduction Target” in February 2015 to set out targets for risk reduction during the decommissioning of TEPCO’s Fukushima Daiichi Nuclear Power Station. It is reviewed regularly and the achievement statuses of the targets are evaluated.

18 February, 2015



# Concepts of the Revision of March 2018 Version



- Characters of the risk reduction target:  
Focusing on presenting the residual risks, in addition that has the characters of the risk reduction work processes.
- Targets to be noted:  
In principle, targets with high risks concerning radioactive substances are noted, as well as targets of high interest for the completion of decommissioning.
- Target period:  
Approximately three years.
- Targets' position on the timeline:  
To be placed at the expected time of completion.


# Revision of Mid-term Risk Reduction Target



- Based on concepts of the revision, the contents of the documents are as follows:
  - Mid-term Risk Reduction Target for TEPCO's Fukushima Daiichi Nuclear Power Station (March 2018 version)
  - Conceptual diagram of main risks, etc. for the beginning of FY2018 and the end of FY2020 [p. 6, 7]
  - Specific processes for mid-term risk reduction of TEPCO's Fukushima Daiichi Nuclear Power Station [p. 8, 9]

# Mid-term Risk Reduction Target for TEPCO's Fukushima Daiichi Nuclear Power Station (March 2018 version)


March 7, 2018  
Nuclear Regulation Authority






# Conceptual Diagram of Main Risks, etc. for the Beginning of FY2018 and the End of FY2020

## TEPCO's Fukushima Daiichi Nuclear Power Station Beginning of FY2018



# Conceptual Diagram of Main Risks, etc. for the Beginning of FY2018 and the End of FY2020

## TEPCO's Fukushima Daiichi Nuclear Power Station The End of FY2020





# Specific Processes for Mid-term Risk Reduction for TEPCO's Fukushima Daiichi Nuclear Power Station (excerpt)

## Unit 3

Main category	Sub-category	Completed measure	Schedule (fiscal year)				
			2018	2019	2020	2021	2022
Liquid radioactive waste	Treatment of accumulated contaminated water	<ul style="list-style-type: none"> <li>Treatment accumulated contaminated water of inside the condenser (December 2017)</li> </ul>			<div style="border: 1px dashed red; padding: 2px;">Decide on the strategy of fuel debris cooling</div> <div style="border: 1px dashed red; padding: 2px;">Adopt air cooling for fuel debris</div> <div style="border: 1px dashed red; padding: 2px;">Treat accumulated contaminated water of inside the reactor building (R/B)</div>		
	No additional accumulated contaminated water (restraining the inflow of groundwater, rainwater, cooling water, and work-use water)			<div style="border: 1px dashed blue; padding: 2px;">Adopt full circulation of fuel debris cooling water</div>	<div style="border: 1px solid blue; padding: 2px;">Treat accumulated contaminated water inside the turbine building (T/B) and waste treatment building (Rw/B) [until the first half of FY2020]</div> <div style="border: 1px solid blue; padding: 2px;">Restrain the inflow of ground water into the turbine building [until the first half of FY2020]</div>	<div style="border: 1px dashed blue; padding: 2px;">Repair the roof of the waste treatment building</div> <div style="border: 1px dashed blue; padding: 2px;">Restrain the inflow of groundwater after completing the treatment of accumulated contaminated water, excluding Units 1 to 3</div>	
Spent fuel pool	Removal of spent fuels	<ul style="list-style-type: none"> <li>Installation of cover (February 2018)</li> </ul>	<div style="border: 1px solid blue; padding: 2px;">Train staff, remove small rubble, etc. [until around the middle of FY2018]</div>	<div style="border: 1px solid blue; padding: 2px;">Remove spent fuels [from the middle of FY2018 to the end of FY2020]</div>	<div style="border: 1px dashed blue; padding: 2px;">Remove used control rods</div>	<div style="border: 1px dashed blue; padding: 2px;">Drain water</div>	
Earthquake/ tsunami	Earthquake			<div style="border: 1px dashed blue; padding: 2px;">Decide upon the strategy on the seismic motion for review (observing the status of containment vessels, such as suppression chambers)</div>			
	Tsunami		<div style="border: 1px solid blue; padding: 2px;">Block the openings of Unit 3 Turbine Building [until the first half of FY2018]</div>				
Decommissioning/ facility investigation	Facility investigation	<ul style="list-style-type: none"> <li>Investigation inside the containment vessel (October 2015)</li> <li>Investigation inside the pedestal (July 2017)</li> </ul>	<div style="border: 1px dashed blue; padding: 2px;">Investigate inside the containment vessel</div>				



# Specific Processes for Mid-term Risk Reduction for TEPCO's Fukushima Daiichi Nuclear Power Station (excerpt)

## Common

Main category	Sub-category	Completed measure	Schedule (fiscal year)					
			2018	2019	2020	2021	2022	2023
Liquid radioactive waste	Treatment of accumulated contaminated water	<ul style="list-style-type: none"> <li>Restraint of the outflow of accumulated contaminated water inside the buildings</li> </ul>	Reduce the amount of radioactive substances to half or less					
	Restraint of water contamination		Increase pump capacity of the sub-drain [until January 2018] → [until June 2018]	Facings of ground level 2.5, 6, 8.5m, etc.	Restrain the inflow of groundwater after completing the treatment of accumulated contaminated water, excluding Units 1 to 3 Reactor Buildings	Facings around the buildings, etc.		
	Treatment of accumulated contaminated water in tanks	<ul style="list-style-type: none"> <li>Removal of horizontal tanks (December 2014)</li> <li>Removal of accumulated contaminated water (RO concentrated water) from flange-type tanks (May 2015)</li> </ul>	Treat accumulated contaminated water (Sr treated water) in flange-type tanks [until October 2018]					
	Removal of accumulated water			Remove accumulated contaminated water on the premises, etc.			Remove underground cisterns	
Earthquake/ tsunami	Earthquake			Dismantle the upper part of the exhaust stack on Units 1 and 2 [until the second half of FY2019]			Take measures against the deterioration of building structures	
	Tsunami	<ul style="list-style-type: none"> <li>Installation of temporary seawalls (June 2011)</li> <li>Blocking openings Common pool (September 2013); Units 1 and 2 Turbine Buildings, high-temp. incinerator (October 2014)</li> </ul>	Block openings of the process main building [until the first half of FY2018]	Decide on the strategy of measures for Mega-Float		Transfer sludge from decontamination instruments (AREVA) [until the second half of FY2020]	Take measures for Mega-Float	



# Priority Targets

## (Treatment of Accumulated Contaminated Water)



- **NRA recognizes that, in order to reduce the risk of accumulated contaminated water in buildings, which is high concentration liquid radioactive waste, flowing out, the treatment of accumulated contaminated water must be conducted promptly.**
- **Complete the treatment of accumulated contaminated water in buildings, excluding the reactor buildings, within 2020.**
  - In the 12th Extraordinary Meeting of NRA held in May 2018, the president of Fukushima Daiichi Decontamination & Decommissioning Engineering Company Mr. Ono stated that he “will achieve this goal at any cost.”
  - As the amount of accumulated contaminated water in buildings is treatable within approximately one month if the currently installed multi-nuclide removal systems are operated at full capacity, the treatment should be conducted immediately.

The amount of accumulated contaminated water as of July 2018: Approx. 50,000 m<sup>3</sup> ÷ ALPS total capacity: 2,000 m<sup>3</sup>/day = 25 days?  
(Existing: 750 m<sup>3</sup>/day, additional: 750 m<sup>3</sup>/day, high performance: 500 m<sup>3</sup>/day)
  - TEPCO should consider operating the currently stopped high performance multi-nuclide removal systems and moving up the schedule so that the treatment can be completed prior to 2020.
- **Complete the treatment of treated water with Sr contained in the flange-type tank by November 2018.**
  - The treatment plan for treated water with Sr is approximately one month behind schedule. To avoid further delays, TEPCO should establish backup systems to prevent unexpected events from affecting the treatment plan.

The amount of treated water with Sr stored in the flange-type tank as of June 2018: Approx. 50,000 m<sup>3</sup>



# Priority Targets (Liquid Radioactive Waste)



➤ **NRA recognizes that, in order to avoid the risk of leakage of high concentration liquid radioactive waste caused by Tsunami, the waste must be transferred to a higher ground and stabilized promptly.**

➤ **Complete the transfer of AREVA sludge to higher ground.**



- Although the transfer is scheduled to be completed within FY2020, TEPCO should consider completing the transfer as early as possible from the perspective of countermeasures against Tsunami.

➤ **Install a stabilization system for AREVA sludge.**

- While the research and development of stabilization treatment has been underway, the installation plan for the stabilization system must be formulated at an early stage, and the timing at which the operation can be started must be clarified.

➤ **Install a stabilization system for ALPS slurry (HIC), etc.**

- Preparation, such as moving up the schedule to prevent delay in the start of operation of the treatment system, must be done steadily, so that the approval of changes on the implementation plan can be requested at an early stage.



Storage condition

Main component		Concentration of major nuclide	Generation rate
Existing ALPS	Iron co-precipitation slurry: FeO (OH) / H <sub>2</sub> O (75%)	<sup>90</sup> Sr: Approx. $1 \times 10^6$ Bq/cm <sup>3</sup>	386 HIC units 1,008 m <sup>3</sup>
Existing ALPS Additional ALPS	Carbonate slurry: CaCO <sub>3</sub> , Mg(OH) <sub>2</sub>	<sup>90</sup> Sr: Approx. $4 \times 10^7$ Bq/cm <sup>3</sup>	971 HIC units 2,535 m <sup>3</sup> 1121 HIC units 2,926 m <sup>3</sup>





# Priority Targets (Treated Water by Multi-nuclide Removal System)



- NRA recognizes that a decision on discharging treated water that contains tritium to the sea, etc. in accordance with the regulatory standards must be made as soon as possible for the decommissioning work.
- As for the long-term storage of tritium-containing treated water in several hundred tanks (approx. 900 units), the possibility of leakage to the environment due to earthquakes, etc. cannot be ruled out. The environmental impact of it leaking into the environment is small; however, economic damage may be incurred as a result of rumors.
- TEPCO should consider all the possibilities and take countermeasures. TEPCO should immediately address specific countermeasures for handling treated water that contains tritium.
- TEPCO should have awareness as the responsible body and proactively make the decision to progress the decommissioning work.



Image: Google Map




# Priority Targets (Others)




➤ **Start the removal of spent fuels from Unit 3 from the November 2018.**

- Although the malfunction of the crane of the fuel handling machine is said to have affected the schedule for removal of spent fuels, removal must be started in November 2018 as planned.



➤ **Complete the dismantling of the upper part of the exhaust stack for Units 1 and 2 by the second half of FY2019.**

- As for the exhaust stacks to which damage due to earthquakes has been confirmed, dismantling work must be started in December 2018 and carried out as planned.



➤ **Evaluate the seismic resistance of the containment vessels (suppression chambers, etc.) using the earthquake for review.**

- The evaluation of earthquake resistance must be conducted immediately, since the suppression chamber is currently filled with contaminated water and considering the damage caused by earthquakes and corrosion, there is a safety concern in the event of occurrence of earthquakes of the same level as the 3.11 earthquake.





# Summary



- ✓ TEPCO needs to implement the items indicated in the Mid-term Risk Reduction Target in a planned and steady manner.
- ✓ The Nuclear Regulation Authority will continue to monitor and evaluate that risk reduction is implemented without delay.
- ✓ In particular, move up the schedules for the treatment of accumulated contaminated water in buildings, transfer of AREVA sludge, and removal of spent fuels in Unit 3. Decisions on handling the treated water, such as discharging water treated in the multi-nuclide removal systems to the sea, etc. in accordance with the regulatory standards, should be made as soon as possible.